

# AMCA 210 Series Wind Tunnel Introduction

**Long Win Science & Technology Co., Ltd.**  
**+886-3-4643221**

**E-mail: [longwin@longwin.com](mailto:longwin@longwin.com)**  
**Web Site: [www.longwin.com](http://www.longwin.com)**

**AMCA 210-07 Wind Tunnel**

1985  
**Long Win**  
*Fundamental, Forward & First*

# Content

- 1. AMCA 210 / ISO 5801**
- 2. Principle**
- 3. Operation**
- 4. Calibration**
- 5. Features**
- 6. Application / Q&A**

# *Long Win* – Taiwan



# Long Win Introduction

Expert in:

1. Electronics **thermal management**.
2. Mechanics and manufacture engineering.
3. Control field technologies.
4. More than **600** system design experiences.
5. More than **2000 m<sup>2</sup>** **fluid and thermal lab**.



# AMCA 210 Standard

## Lab. Methods of Testing Fans for Aerodynamic Performance Rating

Published by

**ANSI/AMCA 210-07**

**ANSI/ASHRAE 51-2007**

Air Movement and Control Association

American National Standard Institute

American Society of Heating, Refrigerating and Air Conditioning Engineers

AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First

# *Long Win* Wind Tunnel Compliance

## ISO 5801- 2007

Industrial fans -- Performance testing using standardized airways

## AMCA 210- 07

## ASHRAE 51- 07

Laboratory Methods of Testing Fans for Aerodynamic Performance Rating

## GB/T 1236- 2000

## IEC 61591-2005

Household Range Hoods - Methods for Measuring Performance

## JIS B 8330

*Long Win*

## AMCA 210-07 Series Wind Tunnel

[Introduction](#) | [Principle](#) | [Operation](#) | [Calibration](#) | [Features](#) | [Model](#)



AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First

## AMCA 210-99 Wind Tunnel Introduction

Wind Tunnel with  
Flow / Pressure Measuring Mode

### A. Flow Measuring Mode:

Low Cost.

Large Uncertainty.


### B. Pressure Measuring Mode:

Higher Cost to Compare with A Mode.

Higher Accuracy and Repeatability.

## A. Flow Measuring Ducts

Circular Cross-section, 24 Points Measuring.  
AMCA 210-99 Fig. 7、13、16 Structure.




$$Q = U_{\text{duct}} \times A_{\text{duct}}$$

$U_{\text{duct}}$  : Average Velocity.

$A_{\text{duct}}$  : Cross-section .

$Q$  : Volume Flow rate.





# Introduction | Principle | Operation | Calibration | Features | Model

## Flow Mode | Pressure Mode | Installation Type




Figure 7 Outlet Duct  
ANSI/AMCA STANDARD 210-85




Figure 13 Inlet Chamber  
ANSI/AMCA STANDARD 210-85




Figure 16 Inlet Duct  
ANSI/AMCA STANDARD 210-85

## B. Pressure Measuring Mode:

Duct & Chamber to Measuring the Pressure Difference Across the Nozzle( $\Delta P_{56}$ ) to Calculate the Air Flow Rate.

Fig.8~12 , 14 , 15 Structure.

$$Q_N = C_d \times U_n \times A_n \quad \text{single nozzle}$$
$$Q_T = \sum Q_N \quad \text{multi-nozzle}$$


$C_d$  : Discharge Coefficient.

$U_n$  : Velocity at Nozzle Throttle.

$A_n$  : Nozzle Throttle Cross-section.

$Q_N$  : Single Nozzle Air Flow Rate

$Q_T$  : Multi Nozzle Air Flow Rate.



$\Delta P$  Across the Nozzle

**Flow Mode** | **Pressure Mode** | **Installation Type**




Figure 8 Outlet Duct  
ANSI/AMCA STANDARD 210-85




Figure 9 Outlet Duct  
ANSI/AMCA STANDARD 210-85




Figure 10 Outlet Duct  
ANSI/AMCA STANDARD 210-85




Figure 11 Outlet Chamber  
ANSI/AMCA STANDARD 210-85

# Introduction | Principle | Operation | Calibration | Features | Model

## Flow Mode | Pressure Mode | Installation Type




Figure 12 Outlet Chamber  
ANSI/AMCA STANDARD 210-85




Figure 14 Inlet Chamber  
ANSI/AMCA STANDARD 210-85





Figure 15 Inlet Chamber  
ANSI/AMCA STANDARD 210


# Introduction | Principle | Operation | Calibration | Features | Model

## Flow Mode | Pressure Mode | Installation Type




**Type A**

Free Inlet,  
Free Outlet




**Type B**

Free Inlet,  
Ducted Outlet



**Type C**

Ducted Inlet,  
Free Outlet



**Type D**

Ducted Inlet,  
Ducted Outlet






Fig.12 12025 DC12V with Different Type




Fig.12/15 8038 DC12V with Different Type




Fig.12/15 8038 DC12V with Type A






Fig.12/15 8038 DC12V with Type B





## Outlet Chambers


An outlet chamber (Figure 11 or 12) shall have a cross-sectional area at least **nine times** the area of the fan outlet or outlet duct for fans with axis of rotation perpendicular to the discharge flow and a cross-sectional area at least **sixteen times** the area of the fan outlet or outlet duct for fans with axis of rotation parallel to the discharge flow.

## Inlet Chambers

Inlet chambers (Figure 13, 14, or 15) shall have a cross-sectional area at least **five times** the fan inlet area.

From AMCA 210-99 page10






different chamber shapes

A chamber may have a **circular** or **rectangular** cross-sectional shape.

The dimension M in the test setup diagram is the inside diameter of a circular chamber or the equivalent diameter of dimensions a and b where

$$M = \sqrt{\frac{4ab}{\pi}}$$

From AMCA 210-99 Page10




Any combinations of screens or perforated plates that will meet these requirements may be used, but in general a reasonable chamber length for the settling means is necessary to meet both requirements.

Screens of square mesh round wire with **open areas of 50% to 60% are suggested** and several will usually be needed to meet the above performance specifications.

A performance check will be necessary to verify the flow settling means are providing proper flow patterns.

From AMCA 210-99




## Upstream Settling Means

Where a measuring plane is located upstream of the settling means, the purpose of the settling screen is to absorb the kinetic energy of the upstream jet, and allow its normal expansion as if in an unconfined space.

This requires some backflow to supply the air to mix at the jet boundaries, but the maximum reverse velocity shall not exceed 10% of the calculated Plane 2 or Plane 6 mean jet velocity.

From AMCA 210-99



## Downstream Settling Means

Flow settling means shall be installed in chambers where indicated on the test setup figures to provide proper airflow patterns.


Where a measuring plane is located downstream of the settling means, the settling means is provided to ensure a substantially uniform airflow ahead of the measuring plane.

In this case, the maximum local velocity at a distance 0.1 M downstream of the screen shall not exceed the average velocity by more than 25% unless the maximum local velocity is less than 2 m/s (400 fpm).

From AMCA 210-99

## Notes


1. Nozzle throat dimension  $L$  shall be either  $0.6D \pm 0.005D$  (recommended) or  $0.5D \pm 0.005D$ .
2. Nozzle shall have elliptical section as shown. Two and three radii approximations to the elliptical form that do not differ at any point in the normal direction more than  $1.5\% D$  from the elliptical form may be used. The outlet edge of the nozzle shall be square, sharp, and free from burrs, nicks or roundings.
3. The nozzle throat shall be measured (to an accuracy of  $0.001 D$ ) at the minor axis of the ellipse and the nozzle exit. At each place, four diameters—approximately  $45^\circ$  apart must be within  $\pm 0.002 D$  of the mean. At the entrance to the throat the mean may be  $0.002 D$  greater, but no less than the mean at the nozzle exit.

[>> Next Page](#)



## Notes


- The nozzle surface shall fair smoothly so that a straight-edge may be rocked over the surface without clicking and the surface waves shall not be greater than  $0.001 D$  peak to peak.
- When nozzles are used in a chamber, either of the types shown above may be used. Where a nozzle discharges directly to a duct, nozzles with throat taps shall be used, and the nozzle outlet should be flanged.
- Throat tap nozzles shall have four static pressure taps  $90^\circ$  apart connected to a piezometer ring.



From AMCA210-99

[<< Previous Page](#)

### 6.3.4 Multiple Nozzles.



Multiple nozzles shall be located as symmetrically as possible. The centerline of each nozzle shall be at least 1.5 nozzle throat diameters from the chamber wall.

The minimum distance between centers of any two nozzles in simultaneous use shall be three times the throat diameter of the larger nozzle.

The uncertainty of the airflow rate measurement can be reduced by changing to a smaller nozzle or combination of nozzles for the lower airflow rate range of the fan.

From AMCA210-99

## Pressure Measuring Mode

Single Nozzle :  $Q_N = C_d \times U_n \times A_n$


Multi-Nozzle :  $Q_T = \sum Q_N$

Where

$C_d$  = Discharge Coefficient

$U_n$  = Throat Velocity

$A_n$  = Throat Cross Section



[How to get  \$C\_d\$](#)

[How to get  \$U\_n\$](#)





Figure 18 Coefficients of Discharge For Flow Nozzles

From AMCA 210-85 Page 38

$$C_d = 0.9986 - \frac{7.006}{\sqrt{Re}} + \frac{134.6}{Re}$$

$$Re = \frac{D_n \cdot U_n}{\nu}$$

[Back to Nozzle Flow Rate](#)



From AMCA210-99

$$U_n = \sqrt{\frac{2 \times \Delta P_n}{\rho}}$$

Where


$U_n$  = Throat velocity  $\Delta P_n$

= Pressure difference between PL5 and PL6

$\rho$  = Air flow density


[Back to Nozzle Flow Rate](#)

**Step 1 : Power ON. (Push ON/OFF button)**  
( equipment will warm up 3 minutes )





## Step 2 : Check Control Mode at PC position



### Step 3 : Software click system auto zero

Welcome to LW-9015 RSAN Series V6: Nov 28 2009  
Air Flow Rate & Pressure Measurement Apparatus  
**Meet AMCA 210-99 Standard**  
Model Selection


	Model	Air Flow Rate
<input type="radio"/>	LW-9014N	0.2~10CFM
<input type="radio"/>	LW-9081	1.6~60CFM
<input checked="" type="radio"/>	LW-9015	2.4~250CFM
<input type="radio"/>	LW-9185	2.9~800CFM
<input type="radio"/>	LW-9120	20~1000CFM
<input type="radio"/>	LW-9125	60~3000CFM
<input type="radio"/>	LW-----	-----

**LonGwin**

Exit      System Auto Zero


Next

**Step 4 : System turn on all valves, warm up 180 sec,  
P1 / P2 / P3 auto zero**



Step 5 : System auto zero completed  
Click Stop for next step





**Fig.15 Inlet Chamber**

D. Fan Performance Curve - FPC

E. System Resistance Curve - SRC

F. Airflow / Thermal Resistance - TRC

**Fig.12 Outlet Chamber**

A. Fan Performance Curve - FPC

B. System Resistance Curve - SRC

C. Airflow / Thermal Resistance - TRC



**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
<input type="button" value="Constant Volt"/>	<input type="button" value="Constant Volt"/>	<input type="button" value="Constant RPM"/>
<input type="button" value="PWM"/>	<input type="button" value="Cpk"/>	<input type="button" value="Operation Point Check"/>
<input type="button" value="Constant RPM"/>	<input type="button" value="Operation Point Check"/>	
<input type="button" value="Cpk"/>		
<input type="button" value="Operation Point Check"/>		

DC Fan Power Supply Output Max. Limit (Volt)

Inlet Area(cm<sup>2</sup>):

Outlet Area(cm<sup>2</sup>):

☐ Manual Voltage Control    number of times:     ☒ Continue

   Voltage (V)    Start     Step     Stop

	1	2	3	4	5	6	7	8	9	10
Voltage										



**(1) Constant Volt - step mode**

[Back to Operation](#)

Fan & Fan Tray Performance Test

DC Power	AC Power	External Driving Power
<input type="button" value="Constant Volt"/>	<input type="button" value="Constant Volt"/>	<input type="button" value="Constant RPM"/>
<input type="button" value="PWM"/>	<input type="button" value="Cpk"/>	<input type="button" value="Operation Point Check"/>
<input type="button" value="Constant RPM"/>	<input type="button" value="Operation Point Check"/>	
<input type="button" value="Cpk"/>		
<input type="button" value="Operation Point Check"/>		

DC Fan Power Supply Output Max. Limit  Volt

Inlet Area(cm<sup>2</sup>):

Outlet Area(cm<sup>2</sup>):

☒ STEP INDICATED

☐ Manual command control    number of times:

Voltage (V)    Start     Step     Stop

	1	2	3	4	5	6	7	8	9	10
Voltage	6.00	8.00	9.00	12.00						

**(1) Constant Volt - Indicated mode**

[Back to Operation](#)

Fan & Fan Tray Performance Test

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

DC Fan Power Supply Output Max. Limit: 15.0 Volt

Inlet Area(cm<sup>2</sup>): 64.00

Outlet Area(cm<sup>2</sup>): 64.00

☐ Manual command control number of times: 1

Voltage (V) Start: 10.00 Step: 1.00 Stop: 12.00

	1	2	3	4	5	6	7	8	9	10
Voltage	6.00	8.00	9.00	12.00						

External Device Setting

Discard Back Next

**(1) Constant Volt**

[Back to Operation](#)

Fan & Fan Tray Performance Test

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

DC Fan Power Supply Output Max. Limit: 15.0 Volt      Inlet Area(cm<sup>2</sup>): 64.00  
Outlet Area(cm<sup>2</sup>): 64.00

☒ Manual command control      number of times: 1

STEP INDICATED:


Voltage (V)      Start: 12.00      Step: 1.00      Stop: 12.00

	1	2	3	4	5	6	7	8	9	10
Voltage	6.00	8.00	9.00	12.00						


External Device Setting

Discard      Back      Next

## (1) Constant Volt




### (1) Constant Volt






### (1) Constant Volt


[Back to Operation](#)





### (1) Constant Volt

[Back to Operation](#)


### (1) Constant Volt

[Back to Operation](#)


### (1) Constant Volt

[Back to Operation](#)


## (2) PWM

[Back to Operation](#)




**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
<b>PWM</b>	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

DC Fan Power Supply Output Max. Limit:  Volt

Inlet Area(cm<sup>2</sup>):

Outlet Area(cm<sup>2</sup>):

**STEP  
INDICATED**

Voltage (V)	Start	<input type="text" value="5.00"/>	Step	<input type="text" value="1.00"/>	Stop	<input type="text" value="15.00"/>
Frequency (KHz)	Start	<input type="text" value="10.00"/>	Step	<input type="text" value="10.00"/>	Stop	<input type="text" value="100.00"/>
Duty (%)	Start	<input type="text" value="5"/>	Step	<input type="text" value="10"/>	Stop	<input type="text" value="100"/>


	1	2	3	4	5	6	7	8	9	10
Freq.										

	1	2	3	4	5	6	7	8	9	10
Duty										


Discard Back Next



## (2) PWM




### (2) PWM





### (2) PWM




# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

## [Warm Up](#) | **Operation>> (A/D) fan & fan tray performance test**

[Back to Top](#)

### **(2) PWM**

[Back to Operation](#)




# Introduction | Principle | Operation | Calibration | Features | Model

## Warm Up | Operation>> (A/D) fan & fan tray performance test

[Back to Top](#)

### (2) PWM

[Back to Operation](#)




# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (A/D) fan & fan tray performance test**

[Back to Top](#)

## (2) PWM

[Back to Operation](#)





### (3) Constant RPM

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
<input type="button" value="Constant Volt"/>	<input type="button" value="Constant Volt"/>	<input type="button" value="Constant RPM"/>
<input type="button" value="PWM"/>	<input type="button" value="Cpk"/>	<input type="button" value="Operation Point Check"/>
<input checked="" type="button" value="Constant RPM"/>	<input type="button" value="Operation Point Check"/>	
<input type="button" value="Cpk"/>		
<input type="button" value="Operation Point Check"/>		

DC Fan Power Supply Output Max. Limit:  Volt

Inlet Area(cm<sup>2</sup>):

Outlet Area(cm<sup>2</sup>):

STEP

INDICATED

☒ Mode1 : Constant RPM with Voltage Regulate

☐ Mode2 : Constant RPM with Constant Voltage

☐ Mode3 : Constant RPM with Duty Regulate

☐ Mode4 : Assign RPM at free delivery (Qmax)

☐ Mode5 : Server motor control

Tolerance(%)


RPM Start  Step  Stop

	1	2	3	4	5	6	7	8	9	10
RPM										

Fan Test Voltage - Low:  Volt


Fan Test Voltage - High:  Volt

### (3) Constant RPM







### (3) Constant RPM



### (3) Constant RPM



### (3) Constant RPM




# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (A/D) fan & fan tray performance test**

[Back to Top](#)

## **(3) Constant RPM**

[Back to Operation](#)





**(4) CPK test**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

DC Fan Power Supply Output Max. Limit: 15.0 Volt

Inlet Area(cm<sup>2</sup>): 64.00

Outlet Area(cm<sup>2</sup>): 64.00

☒ Default

Spec. = Average value  
Tolerance = 3 sigma

Constant Voltage

☒ Indicated mode: 6.00 Volt

Cpk execution cycles: 35

☐ Input Values

Item	Spec.	Tolerance +	Tolerance -
Item A: Fan Air Flow Rate(CFM)	110.83	0.72	0.72
Item B: Fan Static Pressure(mmAq)	6.70	0.06	0.06
Item C: Fan RPM	4040	66	64
Item D: Fan Current (Amp)	1.01	0.06	0.06

Discard Back Next

# Introduction | Principle | Operation | Calibration | Features | Model

Warm Up | Operation>> (A/D) fan & fan tray performance test


[Back to Top](#)

## (4) CPK test


[Back to Operation](#)

Engineering Specification				
	A	B	C	D
product spec	23.0896	2.72743	2648.09	0.114
+ Tolerance	0.92445	0.06015	23.6424	0.17102
- Tolerance	0.92445	0.06015	23.6424	0.17102
USL	24.014	2.78758	2671.73	0.28502
LSL	22.1651	2.66728	2624.44	-0.057
Actual Data				
	A	B	C	D
X bar	23.0896	2.72743	2647.07	0.114
Sigma	0.31265	0.02034	7.99585	0.05784
Median	23.029	2.72	2646	0.142
Mode	#N/A	2.72	2645	0.142
Max	23.7085	2.8	2682.5	0.147
Min	22.5752	2.69	2639	0
UCL 3 Sigma	1 Sigma	23.4022	2.74777	2655.07
	2 Sigma	23.7149	2.76811	2663.07
	3 Sigma	24.0275	2.78845	2671.06
LCL 3 Sigma	1 Sigma	22.7769	2.70709	2639.08
	2 Sigma	22.4643	2.68675	2631.08
	3 Sigma	22.1516	2.6664	2623.09
SPC	CP	0.98561	0.98561	0.98561
	CPL	0.98561	0.98561	0.94341
	CPU	0.98561	0.98561	1.02781
	S. CP	0.98561	0.98561	0.94341
	Ca	-3.8E-15	0	-0.0428
	Cpk	0.98561	0.98561	0.94341


Flow rate




Ps (pressure)



RPM



Current (A)





**(5) OP (DC Fan)**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

DC Fan Power Supply Output Max. Limit (Volt)

Inlet Area(cm<sup>2</sup>):

Outlet Area(cm<sup>2</sup>):

DC Power	AC Power	External Power
<input type="checkbox"/> Manual Control	<input type="checkbox"/> Manual Control	
Voltage (Volt) <input type="text" value="10.00"/>	Voltage (Volt) <input type="text" value="100.00"/>	RPM Command <input type="text" value="2000"/>
Frequency (KHz) <input type="text" value="25.00"/>	Frequency (Hz) <input type="text" value="60.0"/>	
Duty (%) <input type="text" value="100"/>		

☒ P-Q Curve with Operation Point Check

Ps(mmHg)  Q(CFM)

**(5) OP (AC Fan)**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

☐ AC - Delta Input (3 Phase)  
☒ AC - Y Input (1 Phase)

Inlet Area(cm<sup>2</sup>): 64.00  
Outlet Area(cm<sup>2</sup>): 64.00

DC Power	AC Power	External Power
<input type="checkbox"/> Manual Control Voltage (Volt): 10.00 Frequency (kHz): 25.00 Duty (%): 100	<input type="checkbox"/> Manual Control Voltage (Volt): 100.00 Frequency (Hz): 60.0	RPM Command: 2000

☒ P-Q Curve with Operation Point Check

Ps(mmHg): 5.00      Q(CFM): 20.00

**(5) OP (Impeller)**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

Inlet Area(cm<sup>2</sup>): 10000.00  
Outlet Area(cm<sup>2</sup>): 10000.00

DC Power	AC Power	External Power
<input type="checkbox"/> Manual Control	<input type="checkbox"/> Manual Control	
Voltage (Volt): 10.00	Voltage (Volt): 100.00	RPM Command: 2000
Frequency (kHz): 25.00	Frequency (Hz): 60.0	
Duty (%): 100		


☒ P-Q Curve with Operation Point Check

Ps(mmAq): 5.00      Q(CFM): 20.00

### (5) OP

## LW-9015RSAN V4 AMCA 210

	Ps mmAq	Ps inAq	Ps_STP mmAq	Q CMM	Q CFM	Q_STP CFM	Fan Speed RPM	Fan Volt V	Fan Amp A
1	3.26	0.13	3.31	0.00	0.00	0.00	2386	11.99	0.106
2	0.00	0.00	0.00	0.98	34.49	34.02	2670	12.00	0.080
3	2.72	0.11	2.76	0.19	6.84	6.75	2446	11.99	0.100
4	2.05	0.08	2.08	0.34	12.03	11.86	2524	11.99	0.093
5	1.82	0.07	1.85	0.39	13.83	13.64	2560	11.99	0.090
6	1.50	0.06	1.52	0.58	20.61	20.33	2596	12.00	0.087
7	0.85	0.03	0.86	0.78	27.56	27.18	2619	11.99	0.084
8									
9									
10									



**(5) OP**

[Back to Operation](#)

Set OP.	Ps (mmAq)	<input type="text" value="2.00"/>	Q (CFM)	<input type="text" value="3.00"/>
Test Fan OP.	Ps (mmAq)	<input type="text" value="4.62"/>	Q (CFM)	<input type="text" value="3.06"/>
Uncertainty	Ps (mmAq)	<input type="text" value="0.06"/>	Q (CFM)	<input type="text" value="0.04"/>

OK  Ps > OP

OP: Operation Point



**(5) OP**

[Back to Operation](#)


Set OP.	Ps (mmAq)	<input type="text" value="6.00"/>	Q (CFM)	<input type="text" value="3.00"/>
Test Fan OP.	Ps (mmAq)	<input type="text" value="4.74"/>	Q (CFM)	<input type="text" value="3.06"/>
Uncertainty	Ps (mmAq)	<input type="text" value="0.06"/>	Q (CFM)	<input type="text" value="0.04"/>

**NG**  **Ps < (OP - Uncertainty)**

OP: Operation Point

(5) OP

[Back to Operation](#)



## (6) AC Constant Volt

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

☒ AC -  $\Delta$  Input  
☐ AC - Y Input

Inlet Area(cm<sup>2</sup>): 64.00  
Outlet Area(cm<sup>2</sup>): 64.00

☐ Manual command control    number of times: 1

STEP INDICATED

Frequency (Hz)	Start	50.0	Step	10.0	Stop	60.0
Voltage (V)	Start	220.00	Step	5.00	Stop	220.00

	1	2	3	4	5	6	7	8	9	10
Voltage										

	1	2	3	4	5	6	7	8	9	10
Freq.										

External Device Setting

Discard    Back    Next

**(6) AC Constant Volt**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

☒ AC - Δ Input  
☐ AC - Y Input

Inlet Area(cm<sup>2</sup>): 64.00  
Outlet Area(cm<sup>2</sup>): 64.00

☐ Manual command control    number of times: 1

STEP INDICATED

Frequency (Hz)    Start: 50.0    Step: 10.0    Stop: 60.0  
Voltage (V)    Start: 220.00    Step: 5.00    Stop: 220.00

	1	2	3	4	5	6	7	8	9	10
Voltage	220.00	220.00	210.00	210.00						
Freq.	50.00	60.00	50.00	60.00						

External Device Setting

Discard    Back    Next

**(6) AC Constant Volt**

[Back to Operation](#)

**Fan & Fan Tray Performance Test**

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

☒ AC -  $\Delta$  Input  
☐ AC - Y Input

Inlet Area(cm<sup>2</sup>): 64.00  
Outlet Area(cm<sup>2</sup>): 64.00

☒ Manual command control number of times: 1

STEP INDICATED

Frequency (Hz) Start: 50.0 Step: 10.0 Stop: 60.0  
Voltage (V) Start: 220.00 Step: 5.00 Stop: 220.00

	1	2	3	4	5	6	7	8	9	10
Voltage	220.00	220.00	210.00	210.00						


	1	2	3	4	5	6	7	8	9	10
Freq.	50.00	60.00	50.00	60.00						

External Device Setting

Discard Back Next



## (6) AC Constant Volt




### (6) AC Constant Volt

#### LW-9015RSAN V7 AMCA 210

**LonGwin**

	Ps mmAq	Q CFM	dP mmAq	Ps_STP mmAq	Q_STP CFM	Fan Speed RPM	Fan Volt V	Fan Amp A
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								



Running Time 
Running  / 
**Fig.12 / FPC**

**Resistance Setting**
Start  Step  Stop  CFM  
Number of times:  Running  CFM

**Offer Airflow Rate**

	Running	Start	Step	Stop
Heater Watt	<input type="text" value="0.00"/>	<input type="text" value="0.00"/>	<input type="text" value="2.00"/>	<input type="text" value="10.00"/>
Flow Rate CFM	<input type="text" value="0.00"/>	<input type="text" value="2.00"/>	<input type="text" value="2.00"/>	<input type="text" value="20.00"/>

**PQ Setting**
Measure Sections 
  
Pmax:  mmAq Qmax:  CFM


Control Mode	Running	Start	Step	Stop
Voltage V	<input type="text" value="0.00"/>	<input type="text" value="12.00"/>	<input type="text" value="1.00"/>	<input type="text" value="12.00"/>
PWM KHz	<input type="text" value="0.00"/>	<input type="text" value="25.00"/>	<input type="text" value="1.00"/>	<input type="text" value="25.00"/>
%	<input type="text" value="0"/>	<input type="text" value="20"/>	<input type="text" value="10"/>	<input type="text" value="100"/>
Revolution rpm	<input type="text" value="0"/>	<input type="text" value="2000"/>	<input type="text" value="2000"/>	<input type="text" value="4000"/>

Name 
  
Td  °C Tw  °C RH  %  
T5  °C T7  °C T8  °C  
Pb  mmHg


M1 M2 M3 M4 M5

**(6) AC Constant Volt**

[Back to Operation](#)




### (6) AC Constant Volt

[Back to Operation](#)





### (6) AC Constant Volt





### (6) AC Constant Volt



**(7) External Constant RPM**

[Back to Operation](#)

Fan & Fan Tray Performance Test

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

Inlet Area(cm<sup>2</sup>) 10000.00  
Outlet Area(cm<sup>2</sup>) 10000.00

STEP INDICATED

RPM Start 1000 Step 200 Stop 1600

RPM	1	2	3	4	5	6	7	8	9	10

Discard Back Next

**(7) External Constant RPM**

[Back to Operation](#)

Fan & Fan Tray Performance Test

DC Power	AC Power	External Driving Power
Constant Volt	Constant Volt	Constant RPM
PWM	Cpk	Operation Point Check
Constant RPM	Operation Point Check	
Cpk		
Operation Point Check		

Inlet Area(cm<sup>2</sup>): 10000.00  
Outlet Area(cm<sup>2</sup>): 10000.00


STEP INDICATED

RPM Start: 1000 Step: 200 Stop: 1600


	1	2	3	4	5	6	7	8	9	10
RPM	800	1000	1500							

Discard Back Next

## (7) External Constant RPM




### (7) External Constant RPM





## (7) External Constant RPM




### (7) External Constant RPM

Td	Tw	RH	T5	T7	T8	Pb	Test Setup	AMCA 210-07 Fig. 15, Inlet Chamber
°C	°C	%	°C	°C	°C	mmHg	Installation	Type A: free inlet, free outlet, CCW, with duct and bell ring
27.3	24.1	77.8	25.0	30.3	29.7	741.9		

Model	Test Condition @ 1760 RPM								
	Ps	Q	P <sub>STP</sub>	Q <sub>STP</sub>	Rotary Speed	Torque	Shaft Power	Ps Efficiency	Pt Efficiency
	Pa	CMH	Pa	CMH	RPM	N-m	Watt	%	%
730/6	1324.8	0	1430.1	0	1763	34.6	6387.9	0.0	0.0
	1138.4	2625	1224.1	2625	1761	31.5	5809.0	14.3	12.9
	1010.8	5129	1081.9	5129	1764	30.3	5597.2	25.7	23.7
	883.2	7711	943.9	7711	1764	28.2	5209.3	36.3	35.1
	686.9	10181	732.7	10181	1762	24.6	4539.1	42.8	42.9
	559.4	12446	595.9	12446	1763	22.1	4080.1	47.4	46.8
	422.0	14824	449.2	14824	1762	20.0	3690.3	47.1	50.6
	304.2	17424	323.8	17424	1761	18.3	3374.7	43.6	54.6
	166.8	20268	177.5	20268	1763	16.8	3101.6	30.3	46.3
	2.4	22925	2.5	22925	1763	14.0	2584.7	0.6	24.5

STP: Standard Air Property is Air at (Td) 20 °C , (RH) 50 % Relative Humidity, and (Pb) 760 mmHg



[Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (A/D) fan & fan tray performance test**

[Back to Top](#)


**(7) External Constant RPM**

[Back to Operation](#)



AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First





# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (B/E) system or module impedance test**


[Back to Top](#)

[Back to Operation](#)

## LW-9015RSAN V7 AMCA 210

**LonGwin**

	Ps mmAq	Q CFM	dP mmAq	Ps_STP mmAq	Q_STP CFM	Fan Speed RPM	Fan Volt V	Fan Amp A
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								



Running Time

Running 0 / 0

Fig.12 / SRC

Name

### Resistance Setting

Start 3.00 Step 3.0 Stop 30.0 CFM  
Number of times: 1 Running 0.0 CFM

### Offer Airflow Rate

	Running	Start	Step	Stop
Heater Watt	0.00	0.00	2.00	10.00
Flow Rate CFM	0.00	2.00	2.00	20.00

### PQ Setting

Measure Sections 7

Pmax: 0.00 mmAq Qmax: 0.00 CFM

Control Mode	Running	Start	Step	Stop
Voltage V	0.00	12.00	1.00	12.00
PWM KHz	0.00	25.00	1.00	25.00
%	0	20	10	100
Revolution rpm	0	2000	2000	4000

Td 25 °C Tw 22 °C RH 50.0 %  
T5 25 °C T7 25 °C T8 25 °C  
Pb 760 mmHg

Setting

M1 M2 M3 M4 M5

New Run Pause Stop Quit

AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First




# [Introduction](#) | [Principle](#) | [Operation](#) | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | [Operation>> \(B/E\) system or module impedance test](#)

[Back to Top](#)

[Back to Operation](#)




# Introduction | Principle | Operation | Calibration | Features | Model

Warm Up | Operation>> (B/E) system or module impedance test

[Back to Top](#)

[Back to Operation](#)



AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First

# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (C/F) offer air flow rate for system testing**

[Back to Top](#)

[Back to Operation](#)

**Step2**

**Offer Air Flow Rate & Dummy Heater Control**

Dimension (mm) a: 80.00 x b: 30.00  
Resistance: 20.00 Ohm  
Sampling Time: 10 Sec  
C1: 2.270 C2: 14.00

Dummy Heater Control Definition

Command	0V	10V
Output	0.0	60.0

$Q_h = C1 \times (T_i - T_u)$   
 $T_c = T_u - (T_i - T_u) / C2$   
 $Q_e = V_{ip} \times I_{ip}$   
 $R_e = (T_c - T_{in}) / Q_e$   
 $R_h = (T_c - T_{in}) / Q_h$   
 $U_c(\text{m/sec}) = 471.94 \times Q_a(\text{CFM}) / (a \times b)$   
 $U_c(\text{LFM}) = U_c(\text{m/sec}) \times 60 / 0.3048$

$R = (T_c - T_{in}) / Q_{line}$  (°C/W)  
Tc Addr: 72 Tdef Addr: 71  
Tin Type: MM2

STEP INDICATED

Air flow rate unit: CFM


Dummy Heater (Watt) Start: 80.00 Step: 10.00 Stop: 80.00  
Air Flow (CFM) Start: 5.00 Step: 5.00 Stop: 30.00  
Step Time (min): 20 (sec): 0  
Cycle Times: 1 Cycle Interval (min): 0  
Hold delay time (min): 1

	1	2	3	4	5	6	7	8	9	10
Barber										
Flow										
Speed										
Control										

Discard Back **Next**

AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First





# Introduction | Principle | Operation | Calibration | Features | Model

Warm Up | **Operation>> (C/F) offer air flow rate for system testing**


[Back to Top](#)

[Back to Operation](#)

## LW-9015RSAN V7 AMCA 210

**LonGwin**

	Ps mmAq	dP [mmAq]	Q [CFM]	Q_STP [CFM]	Tc [C]	Re [C/We]	Rh [C/Wh]	Pd [mmAq]	Pd [InAq]	Uc [m/sec]	Uc [LFM]
1											
2											
3											
4											
5											
6											
7											
8											
9											
10											



Running Time

Running  /

Fig.12 / TRC

### Resistance Setting

Start  Step  Stop  CFM  
 Number of times:  Running  CFM

### Offer Airflow Rate

	Running	Start	Step	Stop
Heater Watt	<input type="text" value="0.00"/>	<input type="text" value="0.00"/>	<input type="text" value="2.00"/>	<input type="text" value="10.00"/>
Flow Rate CFM	<input type="text" value="0.00"/>	<input type="text" value="2.00"/>	<input type="text" value="2.00"/>	<input type="text" value="20.00"/>

### PQ Setting

Measure Sections

Pmax:  mmAq Qmax:  CFM

Control Mode	Running	Start	Step	Stop
Voltage V	<input type="text" value="0.00"/>	<input type="text" value="12.00"/>	<input type="text" value="1.00"/>	<input type="text" value="12.00"/>
PWM KHz	<input type="text" value="0.00"/>	<input type="text" value="25.00"/>	<input type="text" value="1.00"/>	<input type="text" value="25.00"/>
PWM %	<input type="text" value="0"/>	<input type="text" value="20"/>	<input type="text" value="10"/>	<input type="text" value="100"/>
Revolution rpm	<input type="text" value="0"/>	<input type="text" value="2000"/>	<input type="text" value="2000"/>	<input type="text" value="4000"/>

Name

Td  °C Tw  °C RH  %  
 T5  °C T7  °C T8  °C  
 Pb  mmHg

Setting

M1 M2 M3 M4 M5

New Run Pause Stop Quit

AMCA 210-07 Wind Tunnel

1985  
**LonGwin**  
 Fundamental, Forward & First




# [Introduction](#) | [Principle](#) | **Operation** | [Calibration](#) | [Features](#) | [Model](#)

[Warm Up](#) | **Operation>> (C/F) offer air flow rate for system testing**

[Back to Top](#)

[Back to Operation](#)




# Introduction | Principle | Operation | Calibration | Features | Model

Warm Up | Operation>> (C/F) offer air flow rate for system testing

[Back to Top](#)

[Back to Operation](#)



# [Introduction](#) | [Principle](#) | [Operation](#) | [Calibration](#) | [Features](#) | [Model](#)

## [Outgoing Inspection](#) | [Traceability](#)


[Back to Top](#)

[Meters](#) | [Wind tunnel flow calibration & validation](#) | [Create wind tunnel flow impedance database](#)




The quality of our thermometer, pressure, electrical meter (voltage, current, fan speed) will be approved by a third party (SGS) under supervision of Chinese National Laboratory Accreditation (CNLA).

## AMCA 210-99 Wind Tunnel Flow Calibration Process in National Measurement Lab (NML)



## AMCA 210-99 Wind Tunnel Flow Calibration Process in NML



$$\text{Relative error} = \frac{Q_s - Q_m}{Q_m}$$



Wind tunnel calibration Scheme





## Comparison of measurement by NML with other laboratories

Max Flow Rate (m³/h)	Gas	Accuracy (%)	laboratory	Country
1.8×10 <sup>4</sup>	air	±0.28	NML	Taiwan
36	air	±0.03	NMI	Netherland
5000	air	±0.11	NIST	USA
7600	air	±0.08	CEES	USA
130	air	±0.03	CEES	USA
1.0×10 <sup>4</sup>	Natural gas	±0.25	Gaz de France	France
2500	air	±0.1	PTB	Germany
2.0×10 <sup>4</sup>	air	±0.2	QMI	Japan
36	air	±0.2	KRISS	Korea
5.75×10 <sup>5</sup>	Natural gas	±0.25	KMTL	Norway
1.2×10 <sup>4</sup>	air	±0.2	NEL	United Kingdom
1.5×10 <sup>5</sup>	Natural gas	±0.5	BGC	United Kingdom

## Single Nozzle Calibration



## Multi-Nozzles Calibration



## Calibration Report-1

Calibration test result in NML. It provides the correction between standard flow and measurement data. These data can be traced for future calibration.											
Model: LW-9185 800CFM AMCA Wind Tunnel calibration data										date: 06/16/2005	
Measurement data						Standard flow and wind tunnel flow measurement comparison					
No of test	Nozzle	Pressure drop	Barometric Pressure	Wind tunnel Air temp.	Standard flow in CNLA	flow measurement in each nozzle			Sum of each nozzle Qt=Qm1+Qm2+Qm3		Error e=(Qt-Qs)*100/Qs
	diameter	dP	Pb	T5	Qs	Qm1	Qm2	Qm3	Qt		e
	mm	mmAq	mmHg	℃	m³/h	m³/h			m³/h	CFM	%
1	17	31.20	747.3	26.7	17.891	18.0			18.0	10.59	0.6
2		31.20	747.3	26.7	17.891						
3		31.30	747.3	26.7	17.887						
4		72.80	747.2	26.7	27.449	27.6			27.6	16.24	0.5
5		72.70	747.2	26.7	27.442						
6		72.60	747.2	26.7	27.433						
7		121.20	747.2	26.6	35.844	35.6			35.6	20.95	-0.7
8		121.30	747.2	26.6	35.910						
9		121.30	747.2	26.6	35.940						


## Calibration Report-2

10	10 + 17	30.80	747.2	26.7	23.867	6.1	17.8		23.9	14.07	0.1
11		30.90	747.2	26.7	23.914						
12		30.90	747.2	26.7	23.931						
13		70.80	747.2	26.6	36.531	9.3	27.2		36.5	21.48	-0.1
14		70.80	747.2	26.6	36.535						
15		70.85	747.2	26.6	36.536						
16		117.70	747.1	26.6	47.295	12.0	35.1		47.1	27.72	-0.4
17		117.95	747.1	26.6	47.495						
18		118.15	747.1	26.6	47.593						
19	30	30.00	747	26.6	55.366	55.3			55.3	32.55	-0.1
20		30.10	747	26.6	55.512						
21		30.20	747	26.6	55.605						
22		70.00	746.9	26.6	84.462	84.8			84.8	49.91	0.4
23		70.40	746.9	26.6	84.897						
24		70.40	746.9	26.8	85.079						
25		121.50	746.9	26.9	110.865	111.8			111.8	65.80	0.8
26		121.50	746.9	26.9	111.999						
27		121.55	746.9	26.9	112.291						



## Calibration Report-3

28	53	19.90	746.8	26.8	142.059	141.4			141.4	83.23	-0.5
29		20.00	746.8	26.8	142.631						
30		20.00	746.8	26.8	142.855						
31		61.95	746.8	26.9	250.718	250.6			250.6	147.50	0.0
32		62.00	746.8	26.9	251.451						
33		61.90	746.8	26.9	251.485						
34		125.00	746.8	26.8	356.501	355.9			355.9	209.48	-0.2
35		124.85	746.8	26.8	356.232						
36		124.70	746.8	26.8	356.023						
37	84	20.65	746.8	26.8	365.748	363.9			363.9	214.18	-0.5
38		20.60	746.8	26.8	365.300						
39		20.60	746.8	26.8	364.864						
40		65.10	746.9	26.7	645.402	647.9			647.9	381.34	0.4
41		65.00	746.9	26.7	644.682						
42		64.90	746.9	26.7	644.278						
43		122.00	746.9	26.0	878.538	886.3			886.3	521.66	0.9
44		122.00	746.9	26.0	878.364						
45		122.00	746.9	26.0	878.234						




Long Win provides the orifice plate to create original flow impedance curve.

## Traceability

1. Schedule the calibration for thermometers, pressure meters and electrical meters
2. Schedule the wind tunnel flow calibration and validation in third party lab
3. Tracing the wind tunnel flow impedance data with the original database

## Traceability

Long Win provides the orifice plate to measure flow impedance curve for tracing.



## Repeatability

Result of a fan (12025) performance test for 35 times

Flow test data:

110.77	110.77	110.90	111.46	110.71	110.52	110.71	110.64
110.77	110.90	110.83	110.96	110.96	110.77	111.15	110.96
110.96	110.27	111.08	110.96	110.83	111.33	110.96	111.15
111.02	110.90	110.58	110.52	110.83	110.71	110.71	110.45
110.64	110.71	110.64					

$$Q \text{ max variance} = (111.46 - 110.83) / 110.83 = \mathbf{0.57 \%}$$

Pressure test data:

6.73	6.70	6.70	6.70	6.72	6.73	6.71	6.72
6.72	6.73	6.68	6.72	6.72	6.70	6.72	6.76
6.73	6.71	6.74	6.71	6.72	6.73	6.72	6.76
6.73	6.75	6.73	6.70	6.75	6.72	6.73	6.77
6.74	6.74	6.71					

$$P \text{ max variance} = (6.77 - 6.72) / 6.72 = \mathbf{0.74 \%}$$


Max variance:  $\text{Max}[X - X_{\text{bar}}] / X_{\text{bar}}$




## Features

- ☆ **2 in 1** Combine AMCA 210-99 Fig.12 & Fig.15
- ☆ System **Control Automatically**
- ☆ Equipment **Accuracy Certificate**
- ☆ **5 Mode** Fan Performance Curve Test
- ☆ **STP** Conversion
- ☆ **Multi Fan** Performance Curve Test
- ☆ **High Ps** Fan Performance Curve Test
- ☆ System Impedance Curve (**SRC**) Test
- ☆ Thermal Module Performance **R-Q Test** Automatically
- ☆ **QC** – **Cpk** Test
- ☆ **QC** – **Operation Point Check**

## 2 in 1 Combine AMCA 210-99 Fig.12 & Fig.15 Two Structures



AMCA 210 Fig.12 Outlet Chamber Setup Multiple Nozzles in Chamber



AMCA 210 Figure 15 Inlet Chamber Setup Multiple Nozzle in Chamber

## ☆ **System Control Automatically**

- \* Auto Change Nozzles
- \* Auto Switching Ps
- \* Dynamic Scanning and  
Optimize Testing Parameters
- \* Good Gauge R&R  
(Repeatability and Reproducibility)

## ☆ Auto Switching Nozzle Open & Closed



## ☆ Equipment Accuracy Certificate




All meter will be approved by a third party (SGS).



## ☆ Equipment Accuracy Certificate


### Flow Calibration Process in NML




$$\text{Relative error} = \frac{Q_s - Q_m}{Q_m}$$

NML: National Measurement Lab

## ☆ Equipment Accuracy Certificate




## ☆ 5 Mode Fan Performance Curve Test




## ☆ 5 Mode Fan Performance Curve Test



Constant Voltage / PWM



Constant RPM




## ☆ 5 Mode Fan Performance Curve Test





## ☆ 5 Mode Fan Performance Curve Test





Test Fan Op.

Ps	2.69	mmAq
Q	9.97	CFM
Torque	20.62	gr*cm
Input P	2.39	Watt
Fan Input	0.80	Watt
Motor Eff.	33.28	%
Fan Ps Eff.	15.58	%
Overall Eff.	5.18	%


## ☆ 5 Mode Fan Performance Curve Test

Circular duct fan



Different Kind of Fan Test.

## ☆ Fan with Heat Exchanger Performance Test




## ☆ 5 Mode Fan Performance Curve Test




## ☆ 5 Mode Fan Performance Curve Test

AMCA 210-99 Fig.12








## Fan Aerodynamics Performance Test

2000 RPM			
$P_{STP}$	$Q_{STP}$	Torque	N
mmAq	CFM	N-m	RPM
72.25	0.00	10.220	1995
57.72	1369.73	9.300	1999
44.26	2728.86	8.520	2003
30.84	4420.32	7.860	2006
24.66	5700.39	7.970	2006
0.06	8662.61	7.260	2009



# ☆ STP Conversion

## Parameter 1 : Test Condition

Test Condition									
Td	Tw	RH	T5	T7	T8	Pb	Pmax	Qmax	Note
°C	°C	%	°C	°C	°C	mmHg	mmAq	CFM	
Dry-Bulb Temperature	Wet-Bulb Temperature	Relative Humidity	Plane 5 Temperature	Plane 7 Temperature	Plane 8 Temperature	Barometric Pressure			
							21.5	90.00	?
20.3	18.3	82.5	20.1	20.2	20.1	745.5	20.7	94.11	Test Condition
20.0	14.0	50.0	20.0	20.0	20.0	760.0	21.2	91.99	STP
1. <b>Temperature</b> (Td) variation from 5 to 30 °C							Deviation	9.2%	
2. <b>Barometric</b> (Pb) variation from 0.95 to 1.05 atm							Deviation	10.0%	
3. Both <b>Temperature &amp; Barometric</b> variation							Deviation	20.1%	

Axial FAN 8038 AMCA 210 Fig.12 Setup,  
Installation Type B, Constant Voltage DC 12V

( **S** tandard **T**emperature and **P**ressure)

## ☆ STP Conversion

$P_s$		$dP_{56}$	$Q$		$P_{STP}$	$Q_{STP}$
mm A q	inA q	mm A q	CM M	CFM	mm A q	CFM
2.94	0.116	2.9	0.000	0.00	3.14	0.00
1.40	0.055	64.9	0.298	10.52	1.50	10.52
0.00	0.000	38.0	0.674	23.79	0.00	23.79

**From Test Condition convert to Nominal Values (STP).**

**STP:** Standard Air Property is Air at  
 (Td) 20 °C Temperature,  
 (RH) 50 % Relative Humidity,  
 (Pb) 760 mmHg Barometric Pressure.


## ☆ STP Conversion

### Parameter 1 : Test Condition

Blower 6010			
Test No.	P <sub>max</sub>	Q <sub>max</sub>	Input Volt
	mmAq	CFM	Volt
1	11.40	5.02	5.00
3	10.00	4.59	5.00
6	10.34	4.80	5.00

**Same Fan, Same Wind Tunnel,  
Constant Voltage Input.**

**Not Sure Get Same Result**



## ☆ STP Conversion


### Parameter 2 : Installation Type

#### Report Info.


Production Name:	OOO Axial fan		Date:	2008/1/28	
Model Name:	12HDB		Laboratory:	Long Win	
Production size:	8038	(mm)	Test Number:	97001	
Impeller Tip Diameter:	78	(mm)	Curve by:	Eric Feng	
Inlet Area:	64	(cm <sup>2</sup> )	Test Setup:	AMCA 210 Fig.12	
Outlet Area:	64	(cm <sup>2</sup> )	Installation Type:	Type A	
Accessory:			Chamber Corss-section:	1024	(cm <sup>2</sup> )




## ☆ STP Conversion




**Type A**  
**Free Inlet,**  
**Free Outlet**




**Type B**  
Free Inlet,  
Ducted Outlet




**Type C**  
Ducted Inlet,  
Free Outlet



**Type D**  
Ducted Inlet,  
Ducted Outlet




## ☆ STP Conversion



## ☆ STP Conversion

Fig.12/15 8038 DC12V with Type A



## ☆ STP Conversion

### Comparison Methodology

1. Check Same **Installation Type**.
2. Convert PQ Curve from  
**Test Condition** to **STP Condition**.
3. Convert PQ Curve to **Assigned RPM** by Fan Law.

## ☆ STP Conversion

### Test Condition to STP Condition.

Assume Fan constant RPM,  $N_c = N$  at Different Condition

$$Q_c = Q \left( \frac{N_c}{N} \right) \left( \frac{K_p}{K_{pc}} \right)$$

$Q_c / P_{sc}$  : Nominal Values

$$\begin{aligned} P_{sc} &= P_{tc} - P_{vc} \\ &= P_t \left( \frac{N_c}{N} \right)^2 \left( \frac{\rho_c}{\rho} \right) \left( \frac{k_p}{k_{pc}} \right) - P_v \left( \frac{N_c}{N} \right)^2 \left( \frac{\rho_c}{\rho} \right) \end{aligned}$$



From AMCA 210-99 Eq. 8.59~8.62



## ☆ STP Conversion



Td	Tw	RH	T5	T7	T8	Pb	
°C	°C	%	°C	°C	°C	mmHg	
23.8	20.4	73.7	23.9	24.2	23.8	760.5	F
19.7	16.5	72.1	19.3	19.2	19.5	742.6	LongWin

Date:	2008/3/13
Laboratory:	F. VS LongWin
Test Number:	SN9273
Curve by:	Ericfeng
Test Setup:	AMCA 210 Fig.12
Installation Type:	Type A



☆ **STP Conversion**

**Orifice Plate SRC Test**



## ☆ STP Conversion

Test Report ( 1 – 4 )

### Test Condition

Production Name:			Date:	2008/7/9				
Model Name:			Laboratory:	LongWin				
Production size:		(mm)	Test Number:	3846				
Impeller Tip Diameter:		(mm)	Curve by:	Eric				
Inlet Area:	144	(cm <sup>2</sup> )	Test Setup:	AMCA 210 Fig.12				
Outlet Area:	144	(cm <sup>2</sup> )	Installation Type:	Type A				
Accessory:		Chamber Corss-sectional Area:		9216 (cm <sup>2</sup> )				
STP: Standard Air Property is Air at (Td) 20 °C Temperature, (RH) 50 % Relative Humidity, and (Pb) 760 mmHg Barometric Pressur								
Td	Tw	RH	T5	T7	T8	Pb	Pmax	Qmax
°C	°C	%	°C	°C	°C	mmHg	mmAq	CFM
28.1	24.2	73.8	29.2	28.7	23.8	740.9	6.88	94.08

## ☆ STP Conversion

Test Report ( 2 – 4 )

Row Data

Ps		dp	Q		P <sub>STP</sub>		Q <sub>STP</sub>		Rotary Speed
mmAq	inAq	mmAq	CMM	CFM	mmAq	inAq	CMM	CFM	RPM
6.88	0.271	6.54	0.000	0.00	7.31	0.29	0.00	0.00	2380
6.58	0.259	13.10	0.271	9.57	6.99	0.28	0.27	9.57	2582
6.10	0.240	47.43	0.521	18.38	6.48	0.26	0.52	18.38	2694
5.01	0.197	112.26	0.803	28.36	5.32	0.21	0.80	28.36	2814
4.01	0.158	38.61	1.062	37.51	4.26	0.17	1.06	37.51	2892
2.94	0.116	60.35	1.331	46.99	3.12	0.12	1.33	46.99	2975
2.94	0.116	85.65	1.586	56.02	3.12	0.12	1.59	56.02	2864
2.64	0.104	119.86	1.877	66.27	2.81	0.11	1.88	66.27	2722
2.11	0.083	48.14	2.119	74.82	2.24	0.09	2.12	74.82	2714
1.13	0.044	60.89	2.384	84.21	1.20	0.05	2.38	84.21	2770
0.01	0.000	75.94	2.664	94.08	0.01	0.00	2.66	94.08	2845

## ☆ STP Conversion

Test Report ( 3 – 4 )

Row Data

Coverage Factor  $k=2.00$  , Probability 95%


Freq.	R Volt	S Volt	T Volt	Σ Volt	Current	Power	Σ Volt x Current	Power Factor	Air Density	Pv	Pt	Comp. Factor	Pt Eff.	Ps Uncertainty		Q Uncertainty	
Hz	Volt	Volt	Volt	Volt	Amp.	Watt.	VA	PF	kg/m <sup>3</sup>	mmAq	mmAq	Kp	%	± %	± mmAq	± %	± CFM
60	220.0	220.0	219.8	380.9	0.113	18.2	24.86	0.732	1.128	0.00	6.88	0.9998	1.2	1.16	0.079	1.42	0.000
60	220.0	220.0	219.8	380.9	0.109	17.7	23.98	0.731	1.128	0.01	6.59	0.9998	1.6	1.16	0.076	12.17	1.164
60	220.0	220.0	219.8	380.9	0.107	17.2	23.54	0.730	1.128	0.02	6.12	0.9998	3.0	1.17	0.071	3.57	0.656
60	220.0	220.0	220.0	380.9	0.105	16.8	23.10	0.727	1.128	0.05	5.06	0.9998	3.9	1.19	0.060	1.97	0.560
60	220.0	220.0	219.8	380.9	0.104	16.3	22.88	0.712	1.127	0.09	4.10	0.9999	4.4	1.22	0.049	1.62	0.608
60	220.0	220.0	220.0	380.9	0.102	16.0	22.44	0.713	1.127	0.14	3.08	0.9999	4.2	1.31	0.039	1.50	0.706
60	220.0	220.0	219.8	380.9	0.104	16.6	22.88	0.724	1.127	0.19	3.13	0.9999	4.9	1.33	0.039	1.46	0.818
60	220.0	220.0	220.0	380.9	0.107	17.3	23.54	0.734	1.127	0.27	2.91	0.9999	5.1	1.42	0.038	1.44	0.954
60	220.0	220.0	219.8	380.9	0.108	17.3	23.76	0.728	1.127	0.35	2.46	0.9999	4.9	1.64	0.035	1.43	1.070
60	220.0	220.0	219.8	380.9	0.106	17.1	23.32	0.733	1.127	0.44	1.57	0.9999	3.6	2.76	0.031	1.43	1.200
60	220.0	220.0	220.0	380.9	0.105	16.8	23.10	0.727	1.127	0.55	0.56	1.0000	1.4		0.022	1.42	1.338



## ☆ STP Conversion

Test Report ( 4 – 4 )

### Chart




## ☆ **Multi Fan** Performance Curve Test


**Up to 7 Fan.**

( Amp. / Volt. / RPM )

## ★ **Multi Fan** Performance Curve Test



Parallel




Series

## ☆ Multi Fan Performance Curve Test



	Fan1	Fan2
test1	12V	12V
test2	10V	12V
test3	12V	10V

P <sub>STP</sub>	Q <sub>STP</sub>	Fan-Speed	Fan-Volt	Fan-Amp	Volt2	AMP2	RPM2
mmAq	CFM	RPM	Volt	Amp			
40.11	0.00	31867	11.99	0.671	12.06	0.44	29891
37.28	2.20	32576	12.00	0.639	12.06	0.43	29921
35.92	4.73	31325	12.00	0.615	12.06	0.45	28784
35.53	6.58	30526	12.00	0.599	12.05	0.47	27532
35.04	9.18	32658	11.99	0.647	12.04	0.49	26762
34.94	11.21	32643	11.99	0.656	12.04	0.50	26028
33.09	13.64	32261	11.99	0.663	12.03	0.51	25123
35.04	15.51	31269	11.99	0.671	12.02	0.52	24498
30.55	17.71	30666	11.99	0.695	12.02	0.53	24220
23.42	19.90	30501	11.99	0.690	12.02	0.53	23897



## ★ Multi Fan Performance Curve Test









## ☆ **High Ps Fan Performance Curve Test**

**Ps up to 200 mmAq**

## ☆ High Ps Fan Performance Curve Test




## ☆ System Impedance Curve (SRC) Test




## ☆ System Resistance Curve (**SRC**) Test


Vortex diffuser



fire dampers




outside grille




Circular air ducts



Silencers




Air dampers





Air filters

## ☆ SRC : Duct Pressure Drop Test





1. Straight
2. Bend
3. Converge
4. Diverge






- ☆ **Offer Air Flow** Rate Automatically
- ☆ Thermal Module **R-Q Test** Automatically (Option)




# ☆ QC – Cpk Test

Engineering Specification				
	A	B	C	D
product spec	23.0896	2.72743	2648.09	0.114
+ Tolerance	0.92445	0.06015	23.6424	0.17102
- Tolerance	0.92445	0.06015	23.6424	0.17102
USL	24.014	2.78758	2671.73	0.28502
LSL	22.1651	2.66728	2624.44	-0.057
Actual Data				
	A	B	C	D
X bar	23.0896	2.72743	2647.07	0.114
Sigma	0.31265	0.02034	7.99585	0.05784
Median	23.029	2.72	2646	0.142
Mode	#N/A	2.72	2645	0.142
Max	23.7085	2.8	2682.5	0.147
Min	22.5752	2.69	2639	0
UCL 3 Sigma	1 Sigma	23.4022	2.74777	2655.07
	2 Sigma	23.7149	2.76811	2663.07
	3 Sigma	24.0275	2.78845	2671.06
LCL 3 Sigma	1 Sigma	22.7769	2.70709	2639.08
	2 Sigma	22.4643	2.68675	2631.08
	3 Sigma	22.1516	2.6664	2623.09
SPC	CP	0.98561	0.98561	0.98561
	CPL	0.98561	0.98561	0.94341
	CPU	0.98561	0.98561	1.02781
	S. CP	0.98561	0.98561	0.94341
	Ca	-3.8E-15	0	-0.0428
	Cpk	0.98561	0.98561	0.94341


Flow rate




Ps (pressure)




RPM



Current (A)



# ☆ QC – Operation Point Check



Test Fan Op.

$P_s$	2.69	mmAq
$Q$	9.97	CFM
Torque	20.62	gr*cm
Input P	2.39	Watt
Fan Input	0.80	Watt
Motor Eff.	33.28	%
Fan $P_s$ Eff.	15.58	%
Overall Eff.	5.18	%

Operation Point Setting      2.30 mmAq ,      12.00 CFM  
 Test Fan Performance      1.98 mmAq ,      12.05 CFM

**OK**

$P_s > Op.$

**NG**

$(Op.-Uncertainty) > P_s$

## 1. Basic Specifications:

Model	Air Flow Rate ( CFM )	Overall Dimension W x L x H (M)
9014	0.2 ~ 18	0.6 x 3 x 1.6
9081	1.6 ~ 60	0.6 x 3 x 1.6
9015	2.4 ~ 250	0.85 x 3.6 x 1.8
9185	5 ~ 1500	1.2 x 4.6 x 1.9
9120	100 ~ 5000	2.6 x 7 x 2.3
9293	230 ~ 30000 850 CMM	3.0 x 10 x 2.6

## Specifications:

1. Air Flow Rate Range: 0.2 ~ 10 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	3	0.20	0.64	3.5
2	4	0.32	1.15	3
3	5	0.87	1.80	2.5
4	6	1.26	2.60	2
5	8	2.25	4.66	1.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , single phase , 3A.

4. Overall dimension: 0.6 (W) x 3 (L) x 1.6 (H) M.





## Specifications:

1. Air Flow Rate Range: 1.6 ~ 60 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	5	1.5	1.8	3.5
2	6	1.7	2.6	3
3	8	2.5	4.6	2.5
4	14	4.5	14.4	2
5	24	14.5	42.6	1.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , single phase , 3A.

4. Overall dimension:

0.6 (W) x 3 (L) x 1.6 (H) M.



# [Introduction](#) | [Principle](#) | [Operation](#) | [Calibration](#) | [Features](#) | **Model**

[Basic Specification](#) | [9014N-RSAN](#) | [9081RSAN](#) | **[9015RSAN](#)** | [9185RSAN](#) | [9120RSAN](#) | [9125RSAN](#) | [Back to Top](#)



## Specifications:

1. Air Flow Rate Range: 2.4 ~ 250 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	8	2.4	4.6	3.5
2	14	4.5	14.1	3
3	24	13	41	2.5
4	34	26	83	2
5	42	40	127	1.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , single phase , 5A.

4. Overall dimension:

0.85 (W) x 3.6 (L) x 1.8 (H) M.



## Specifications:

1. Air Flow Rate Range: 2.9 ~ 800 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	10	2.9	7.2	3.5
2	17	6.6	20.9	3
3	32	23	73	2.5
4	53	63	202	2
5	84	160	509	1.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , 3 phase , 20A.

4. Overall dimension:

1.2 (W) x 4.6 (L) x 1.9 (H) M.



## Specifications:

1. Air Flow Rate Range: 40 ~ 5000 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	24	20	42	3.5
2	42	41	131	3
3	53	66	209	2.5
4	62	90	287	2
5	72	121	388	1.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , 3 phase , 20A.

4. Overall dimension:

2.6 (W) x 5.2 (L) x 2.3 (H) M.

# [Introduction](#) | [Principle](#) | [Operation](#) | [Calibration](#) | [Features](#) | **Model**

[Basic Specification](#) | [9014N-RSAN](#) | [9081RSAN](#) | [9015RSAN](#) | [9185RSAN](#) | [9120RSAN](#) | **9125RSAN** | [Back to Top](#)



## Specifications:

1. Air Flow Rate Range: 50 ~ 8000 CFM.

2. Nozzle Definition:

NO.	Dimension	Air flow rate		Accuracy
	mm	min.	max.	% INFS
1	40	50	119	3.5
2	70	115	367	3
3	90	188	600	2.5
4	110	282	898	2.5
5	130	395	1256	2.5

**INFS** is the full scale of designated nozzle

3. Power source: AC 220 V , 3 phase , 30A.

4. Overall dimension:

2.6 (W) x 7 (L) x 2.6 (H) M.



## Specifications:

1. Air Flow Rate Range: 230 ~ 30000 CFM.
2. Nozzle Definition:  $\phi$  145 mm X 20 pcs
3. Power source: AC 380 V , 3 phase , 100A.
4. Overall dimension:  
3.0 (W) x 10 (L) x 2.6 (H) M.



# Application

- ☆ **NB** Thermal Design
- ☆ **Server** Thermal Design
- ☆ **Power Supply** Thermal Design
- ☆ **Car Radiator** Thermal Design
- ☆ **Range Hood** Airflow Design
- ☆ **Application** Summary

# Application

[Back to Top](#)


[Back Application](#)

## ★ NB Thermal Design


Step1 :

**Worst case**  
Define mini air flow rate

NB  
Power ON



Offer Air Flow  $Q_{air}$



Temperature  
Data Log

# Application



[Back to Top](#)

[Back Application](#)

## ☆ NB Thermal Design

Step2 :

**NB**  
Flow Impedance



# Application

[Back to Top](#)

[Back Application](#)



## ☆ NB Thermal Design

Step3 :

Step 3

NB  
Blower

AMCA 210-85 Fig.12



AMCA 210-07 Wind Tunnel


1985  
*Long Win*  
Fundamental, Forward & First




# ☆ Server Thermal Design

Step1 :


**Worst case**  
**Define mini air flow rate**



Server



Offer Air Flow  $Q_{air}$






# ☆ Server Thermal Design

Step2 :

## Server Flow Impedance

Server





# ☆ Server Thermal Design

Step3 :


## Check Operation Point

AMCA 210-85 Fig.12







# Server

## Server fan tray case study



# ☆ PSU Thermal Design



## Check Operation Point



## ☆ **PSU Thermal Design**

# Thermal Evaluation

1. Layout scenario analysis
2. Worse case study
3. Cooling method choice
4. HS choice
5. Required cooling airflow rate
6. Airflow impedance (SRC)
7. Fan selection

## ☆ **PSU** Thermal Design




# Thermal Simulation

1. **CFD**
2. **Input / Output**
3. **Tools**

# ☆ PSU Thermal Design

## Thermal Verification

1. IR scanning
2. Temperature testing
3. Airflow testing



## ☆ **PSU Thermal Design**

# **Thermal Verification**


## **Testing Facilities**

- 1. IR Camera**
- 2. Thermocouples / Data Log**
- 3. Worst ambient chamber**
- 4. AMCA 210 wind tunnel**


# ☆ Car Radiator Thermal Design

Step1 :


**Worst case**  
**Define mini air flow rate**



Car Radiator



Offer Air Flow  $Q_{air}$




Temperature  
Data Log




# ☆ Car Radiator Thermal Design

Step2 :

## Car Radiator Flow Impedance



## Car Radiator






# ☆ Car Radiator Thermal Design

Step3 :

## Check Operation Point

AMCA 210-85 Fig.12



# ☆ Range Hood Airflow Design






Fig.12 - Outlet Chamber




## ☆ Range Hood Airflow Design

Fig.15 - Inlet Chamber



O.P.  
**15 CMM at 250 Pa**



## ☆ Range Hood Airflow Design



## Flow Visualization



AMCA 210-07 Wind Tunnel



# Application

## Fan Performance Test



**AMCA 210 Fig.12  
Blow In Test**




**AMCA 210 Fig.15  
Exhaust Test**

## ☆ Fan Performance at High Land

$$Q_2 = Q_1 \times \left( \frac{RPM_1}{RPM_2} \right) \quad P_2 = P_1 \times \left( \frac{RPM_2}{RPM_1} \right)^2 \times \left( \frac{\rho_2}{\rho_1} \right)$$

(A) Constant Fan RPM




$$P_2 = P_1 \times \left( \frac{\rho_2}{\rho_1} \right)$$


1 Sea Level, 2: High Land

## ☆ Fan Performance at High Land

### (B) Constant Fan Voltage




## ☆ Fan Performance at High Land



# System Resistance Test

[Back to Top](#)

[Back Application](#)






[Back to Top](#)

[Back Application](#)

# Server Thermal Test Impedance Test Airflow Test



AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First

[Back to Top](#)

[Back Application](#)

# PSU System Resistance Test



AMCA 210-07 Wind Tunnel

1985  
*Long Win*  
Fundamental, Forward & First


# Thermal Wind Tunnel

## Thermal Test Platform with AMCA 210 Wind Tunnel






# AMCA 210 Link with TTP



## Thermal Module - Thermal Resistance RQ Curve Test





# Heat Exchanger Performance Test



# Heat Exchanger Performance Test



Chiller for Liquid Cooling



Cooling Capacity : 35KW

Temperature Controlled  
Airflow




Heating Capacity :  
30kW-Hr

# Heat Exchanger Performance Test




$\Delta P$ 、 $\Delta T$ 、Cooling Capacity



Cooling Capacity : 40KW  
Liquid Flow : 120 LPM



## ☆ Thermal Module – Performance at High Land



[Back to Top](#)

[Back Application](#)

# Thank you !